

Techline BuyBoard Contract #512-16 01/04/17

San Marcos Little League Complex

San Marcos, Texas

(3)-BASEBALL FIELDS - 225' Radius, ****50/30FC Avg. Light Level****

(1)-BASEBALL FIELD - 310'/350'/310', ****50/30FC Avg. Light Level****

(1)-ALL PURPOSE FIELD - 250' x 250', ****30FC Avg. Light Level****

USING ALL ****METAL HALIDE-1500W Fixtures****

(EXCEPT FOR (1)-225' RADIUS FIELD, WHICH WE WILL USE 750WLED)

Includes 10-Yr Structural/10-Yr Lamp Warranty

Quantity	Description
8	60 Foot Mounling Helght Steel Poles
8	70 Foot Mounling Height Steel Poles
6	7 Fixture Crossarms - Integral Ballast
2	8 Fixture Crossarms - Integral Ballast
2	9 Fixture Crossarms - Integral Ballast
2	6/9 Fixture Back-to-Back Crossarms - Integral Ballast
2	6/8 Fixture Back-to-Back Crossarms - Integral Ballast
1	8/9 Fixture Back-to-Back Crossarms - Integral Ballast
1	9/9 Fixture Bck-to-Back Crossarms - Integral Ballast
32	TSLED 750 Watt Sport LED w/ Visor
137	1500 Watt Metal Halide Integral Ballast Luminaires
137	EcoStar Lenses w/ External Visors
137	1500 watt metal halide lamps
16	Prewiring for Poles and Integral Ballast Crossarms
1	EcoLink Wireless Control System - Base Station
2	EcoLink Wireless Control System - Wireless Node(s) - Wall Mount Near Contactor Cabinet
1	10 Year Lamp Warranty

Total Inc. Turnkey Install = \$479,000.00

Pymnt & Perform. Bond = \$7,100.00

Electrical Engineering = **\$2,500.00**

Grand Total = \$488,600.00

Notes: * Price includes design, poles, prewired crossarms, light fixtures, and lamps.

* Price includes delivery to jobsite.

* Price firm for 30 days.

* Allow 1-2 weeks for delivery and 3-4 weeks for installation.

* Turnkey installation includes:

- Installing new main distribution panel, breakers, contactors and switching based on existing 480V/3Ph service at 4-plex.

- Install new individual conduit and wiring for each pole sized accordingly. No more than 3% voltage drop shall be allowed.

- All wiring to be copper type THHN.

- Includes all permits, fees and inspections associated with the project.

- All electrical installation to meet National Electric Code requirements.

* Standard turnkey and partial install foundations assume 2000 psi soil conditions. Any other conditions that may be present upon installation (i.e. rock, water, etc.) that cause additional foundation design or

modification (i.e. rebar, casing, etc.) may require additional charges.

* Pole locations must also be accessible and not obstructed by fencing, buildings, etc.


* EcoLink Wireless Control Systems include the first 24 months of communication costs.

* Price above does not include SALES or USE taxes.

* A tax exemption certificate must be filed with Techline if applicable.

* All work to be performed that requires a license, including but not limited to electrical & plumbing will be performed by individuals currently licensed in the proper jurisdiction. All proposals are based in bids by licensed individuals anticipated to perform the work.

PREPARED
By:


MARK REYNOLDS

APPROVED
By:


BERT STRATEMAN