



LEGEND

| | |
|---|----------------------------------|
| LOC | LIMITS OF CONSTRUCTION |
| CF | CONSTRUCTION FENCING |
| MS | MULCH SOCK |
| TP | TREE PROTECTION |
| [Stabilized Construction Entrance Symbol] | STABILIZED CONSTRUCTION ENTRANCE |

NOTE:
1. POND TO REMAIN OFFLINE DURING CONSTRUCTION AND UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND PLANTS ARE WELL ESTABLISHED.
2. DEWATERING MUST OCCUR BEFORE ANY CONSTRUCTION ACTIVITY AND NO SEDIMENT LADEN WATER WILL BE DISCHARGED TO THE SAN MARCOS RIVER.

John Gleason LLC

406 LONG BOW LANE
AUSTIN, TEXAS 78704
johngleasonrla@gmail.com



COMPLETE WATERSHED SOLUTIONS
1800 NEW YORK AVENUE
AUSTIN, TEXAS
512-784-2003
lcs@completewatersheds.com

HUTCHISON STREET

BIOFILTRATION POND IMPROVEMENTS

EROSION & SEDIMENTATION CONTROL PLAN

STATE OF TEXAS
LEE SIEMAN
20141
LICENSED PROFESSIONAL ENGINEER

1/11/18