

U.S. FISH & WILDLIFE SERVICE SAN MARCOS, TEXAS

CAPES DAM-BREACH & CHANNEL RESTORATION







NOTES

DAM

1. DAM ELEVATION ~ 552.0 +/- 1' WITH PARTIAL BREACHES EVIDENT DUE TO PARTIAL FAILURE DURING FLOOD.

MILLRACE

BENCH MARK

1. SEE EXISTING SITE PHOTOS 2. BM ELEVATION: 554.4' VD88

ALIGNMENT CENTERLINE LOCATION.

SECTION SAMPLE LINES 1.SECTION LINES WERE SAMPLED AT THREE LOCATIONS ALONG THE ALIGNMENT: UPSTREAM (0 + 12.30), CAPES DAM (0 + 73.38) AND DOWNSTREAM (1 + 17.38). 2. SECTION LINES ARE DISPLAYED ON SHEETS 5 & 6.

ALL ELEVATIONS ARE REPORTED AS FEET TIED TO NGVD 88 DATUM.

1. MILLRACE WIDTH AT CONCRETE HEADWORKS ~ 20' 2. MILLRACE SILL-ELEVATION: 549.0 +/- 1'.

1.ALIGNMENT ORIENTATED AT THE APPROXIMATE CHANNEL 2.ALIGNMENT RUNS FROM STATION 0 + 00 (UPSTREAM LOCATION) TO 1 + 20 (DOWNSTREAM LOCATION). 3.ALIGNMENT SAMPLE POINTS ARE LOCATED AT P.I. POINTS AND DISPLAYED ON SHEET 4.

N MARCO PES DAM ANNEL RI	s, texas E -breach & estoration	XISTING S	SITE ALI(NE SAMPLIN	GNMENT & NG LOCATIONS	SUB-SHEET
SIGNED	DRAWN	CHECKED	DATE	DRAWING NO.	SHEET
STANCILL	W. STANCILL	W. RICE	8/2016	6R-TX-2016-002	2 OF 12

CAPES DAM, ~ 300 CFS, VIEW ACROSS DAM FROM MILLRACE INLET

CAPES DAM, ~ 600 CFS, VIEW ACROSS DAM FROM MILLRACE INLET

CAPES DAM, ~ 600 CFS, VIEW DOWNSTREAM TO UPSTREAM

MILLRACE BENCH MARK CLOSEUP

MILLRACE INLET, VIEW DOWNSTREAM TO UPSTREAM

MILLRACE ENTRANCE, VIEW LEFT BANK TO RIGHT BANK

N MARCOS, TEXAS PES DAM-BREACH & ANNEL RESTORATION	SI	EXISTIN TE PH(NG DTOS	SUB-SHEET
SIGNED DRAWN	CHECKED	DATE	DRAWING NO	SHEET
STANCILL W STANCILL	W RICE	8/2016	GR-TX-2016-002	3 OF 12

EXISTING AND PROPOSED CROSS SECTION PROFILE PARALLEL WITHLONG AXIS OF DAM CENTERLINE

SAN CAP CHA

NOTES:

ELEVATIONS ARE REPORTED AS NGVD-88 AND TIED TO THE BENCHMARK LOCATED ON THE RIGHT BANK OF THE MILL RACE RIGHT BANK CONCRETE WALL. SEE SHEET 3 (EXISTING SITE PHOTOS).

DAM REMOVAL & CHANNEL EXCAVATION

- 1. DAM WILL BE EXCAVATED FROM BANKLINE TO BANKLINE TO AN ELEVATION OF 546.0' OR REFUSAL.
- 2. EXCAVATED BANKLINES WILL BE SLOPED TO ~ 2:1 BUT FOLLOW THE EXISTING BANKLINE CONDITIONS WHERE POSSIBLE.
- 3. ALL EXCESS EXCAVATED MATERIAL WILL BE REMOVED FROM THE CHANNEL AND TRANSPORTED OFF SITE.
- 4. EXCAVATED MATERIAL TRANSPORTED OFF SITE WILL BE NO LARGER THAN 8 CUBIC FT.
- 5. REBAR WILL NOT BE REMOVED FROM EXCAVATED MATERIAL.
- 6. SILT AND OTHER DEPOSITIONAL MATERIAL STORED IN THE RESERVOIR AREA (UPSTREAM OF DAM) WILL NOT BE EXCAVATED.
- 7. THE LÉFT BANK CHANNEL REQUIRES RESTORATION. THIS WORK WILL NOT COMMENCE UNTIL THE EXCAVATED CHANNEL HAS REACHED ITS NEW EQUILIBRIUM (NATURAL GRADE AND PLAN-FORM) AS DETERMINED BY THE US FISH & WILDLIFE SERVICE'S FIELD STAFF.
- 8. IF AND WHEN NEEDED, INSTALL ROCK GRADE CONTROL STRUCTURE AT MILLRACE INLET TO CONTROL HEAD CUTTING AS DEPICTED ON SHEET 7 (BANK STAB & EROSION CONT).

INNEL RESTORATION	ES DAM-BREACH SECTION LINE DETAILS AT DAM	NNEL R		CHECKED	DATE	DRAWING NO.	SHEET	
-------------------	---	--------	--	---------	------	-------------	-------	--

CAPES DAM AREA: EROSION CONTROL INSTALLATION LOCATIONS

SITE

NOTES:

RIGHT BANK REFERS TO RIGHT SIDE OF RIVER LOOKING IN THE DOWNSTREAM DIRECTION.

RIGHT BANK EROSION CONTROL.

- 1. COVER SECTION OF RIGHT BANK EXPOSED DURING DAM REMOVAL WITH JUTE FIBER ROLL.
- 2. JUTE FIBER ROLL MATERIAL EXTENDS LATERALLY ALONG THE BANK FOR ~ 60' AS DEPICTED IN THE ATTACHED PHOTO.

MILL RACE ENTRANCE (ONLY IF NEEDED TO AVOID HEAD CUTTING)

(INSTALL ROCK GRADE CONTROL STRUCTURE, ONLY IF AND/WHEN NEEDED, TO CONTROL HEAD CUTTING INTO THE MILLRACE.

- 1. EXCAVATE MILL RACE ENTRANCE TO ELEVATION 545.0' AND BACKFILL WITH RIP RAP TO ELEVATION 551.0.
- 2. INSTALL 6" OF GRAVEL OVER GEOTEXTILE FILTER FABRIC BEFORE BACKFILLING EXCAVATED AREA WITH RIP RAP.
- 3. RIP RAP EXTENDS HORIZONTALLY ~ 40' FROM BANKLINE TO BANKLINE AS DEPICTED IN THE ATTACHED PHOTO.
- 4. KEY RIP RAP INTO LEFT BANK 5'.
- 5. RIP RAP SHALL BE TIED INTO THE RIGHT BANK (CONCRETE LINED SIDE) TO MAXIMUM POSSIBLE EXTENT WITHOUT EXCAVATING THE CONCRETE.
- 6. ENGINEER WILL STAKE GRADE CONTROL STRUCTURE EXTENTS PRIOR TO CONSTRUCTION.

SAN MARCOS, TEXAS MILL RACE GRADE CONTROL 7 CAPES DAM-BREACH & EROSION CONTROL DETAILS

LOCATIONS DEPICTED ON IMAGE ARE APPROXIMATE. SEE GPS COORDINATES AND PICTURES ON SHEET 9 FOR DETAILED

ACCESS TO STRUCTURES 1, 2, AND 3 ARE GAINED FROM THE STAGING AREA DEPICTED ON SHEET 12.

ACCESS TO STRUCTURE 4 IS GAINED FROM CAPE STREET AS DEPICTED ON SHEET 12.

DEFICIENT STRUCTURE 1 1. LOCATION: -97.931534; 29.872978. 2. STRUCTURE IS A CONCRETE-SLAB COMPROMISED BY BANK

 NO INFORMATION EXISTS ON THE SLABS CONDITION OR EMBEDMENT DEPTH.
 THE CONCRETE-SLAB SHALL BE BROKEN INTO PIECES NO LARGER THAN 8 CUBIC FEET AND EXPORTED OFF SITE.

DEFICIENT STRUCTURE 2. 1. LOCATION: -97.931794; 29.872696. 2. STRUCTURE IS A CONCRETE-SLAB COMPROMISED BY BANK

 NO INFORMATION EXISTS ON THE SLABS CONDITION OR EMBEDMENT DEPTH.
 THE CONCRETE-SLAB SHALL BE BROKEN INTO PIECES NO LARGER THAN 8 CUBIC FEET AND EXPORTED OFF SITE.

DEFICIENT STRUCTURE 3
1. LOCATION: -97.931934; 29.870159.
2. STRUCTURES INCLUDE A CONCRETE BRIDGE AND CONCRETE RUBBLE PLACED ON THE BANK FOR EROSION PROTECTION.
3. NO INFORMATION EXISTS ON THE SLABS CONDITION OR EMBEDMENT DEPTH.
4. THE CONCRETE-SLAB SHALL BE BROKEN INTO PIECES NO LARGER THAN 8 CUBIC FEET AND EXPORTED OFF SITE.

THAN 8 CUBIC FEET AND EXPORTED OFF SITE.

 LOCATION: -97.931456; 29.869921.
 STRUCTURE INCLUDES A DIVERSION STRUCTURE CONSTRUCTED OF CONCRETE.

3. NO INFORMATION EXISTS ON THE STRUCTURES CONDITION OR EMBEDMENT DEPTH.

4. THE STRUCTURE SHALL BE BROKEN INTO PIECES NO LARGER THAN 8 CUBIC FEET AND TRANSPORTED OFF SITE.

N MARCO	S, TEXAS <mark>DEFI</mark> -BREACH & ESTORATION	CIENT INFRAS	STRUCTURE F	REQUIRING REMOVAL DAM REMOVAL	SUB-SHEET
SIGNED	DRAWN	CHECKED	DATE	DRAWING NO	SHEET
STANCILL	W STANCILL	W RICE	8/2016	GR-TX-2016-002	8 OF 13

DEFICIENT STRUCTURE 1. CONCRETE BANK-STABILIZAION STRUCTURE

DEFICIENT STRUCTURE 2. CONCRETE BANK-STABILIZATION STRUCTURE

DEFICIENT STRUCTURE 3. COMPROMISED BRIDGE & BANK-STABILIZATION

DEFICIENT STRUCTURE 4. COMPROMISED WATER CONTROL STRUCTURE

N MARCO APES DAM HANNEL R	^{S, TEXAS} EX –breach & estoration	ISTING SI ⁻	INFRAS TE PHC	STRUCTURE DTOS	SUB-SHEET
SIGNED	DRAWN	CHECKED	DATE	DRAWING NO	SHEET
STANCILL	W STANCILL	W RICE	8/2016	GR-TX-2016-002	9 OF 12

LOCATIONS DEPICTED ON IMAGE ARE APPROXIMATE. SEE GPS COORDINATES AND PICTURES ON SHEET 11 FOR DETAILED LOCATIONS. ACCESS POINT DEVELOPMENT STYLES AND METHODS DEPICTED ON SHEET 11 ARE TYPICAL. ACCESS POINTS WILL BE CONSTRUCTED AS DETERMINED BY THE CITY OF SAN MARCOS.

ACCESS TO POINTS 1, 2, AND 3 WILL GAINED FROM THE STAGING AREA DEPICTED ON SHEET 12.

ACCESS TO POINTS 4 AND 5 ARE GAINED FROM CAPE STREET AS

1. LOCATION: -97.931534; 29.872978. 2. SEE SITE PHOTO ON SHEET 11.

1. LOCATION: -97.931794; 29.872696. 2. SEE SITE PHOTO ON SHEET 11.

1. LOCATION: -97.931914; 29.872242. 2. SEE SITE PHOTO ON SHEET 11.

1. LOCATION: -97.931456; 29.869921. 2. SEE SITE PHOTO ON SHEET 11.

1. LOCATION: -97.930576; 29.869486. 2. SEE SITE PHOTO ON SHEET 11.

N MARCOS PES DAM-	, TEXAS	NEW ACC	SUB-SHEET		
ANNEL RE	STORATION	FUIL	JRE CONSTRU	JUTION	
SIGNED STANCILL	DRAWN W STANCILL	CHECKED W RICE	DATE 8/2016	DRAWING NO GR-TX-2016-002	SHEET 10 OF 12

NEW ACCESS POINT 1, UPSTREAM OF MILLRACE INLET

NEW ACCESS POINT 2; DOWNSTREAM OF MILLRACE INLET

NEW ACCESS POINT 4

NEW ACCESS POINT 5

NEW ACCESS POINT 3

NEW ACCESS POINT DESIGN (TYPICAL)

N MARCOS APES DAM- HANNEL RE	BREACH & STORATION	NEW A SI	CCESS TE PHC	POINTS TOS	SUB-SHEET
SIGNED	DRAWN	CHECKED	DATE	DRAWING NO	SHEET
STANCILL	W STANCILL	W RICE	8/2016	GR-TX-2016-002	11 OF 12

NOTES

LOCATIONS DEPICTED ON IMAGE ARE APPROXIMATE. SEE GPS COORDINATES AND PICTURES FOR DETAILED LOCATIONS. STAGING AREA IS APPROXIMATELY 0.5 ACRES. EQUIPMENT AND MATERIALS WILL BE STORED AT STAGING AREA.

STAGING AREA IS COMPLETED.

1. LOCATION: -97.931534; 29.872978. 2. ACCESS TO STAGING AREA WILL BE GAINED FROM EXISTING TRAIL UNDER THE JURISDICTION OF THE CITY OF SAN MARCOS, TEXAS. 3. STAGING AREA WILL BE REHABILITATED AFTER DECONSTRUCTION

SAN MARCO	S, TEXAS	NEW AC	SUB-SHEET		
CAPES DAM CHANNEL R	-BREACH & ESTORATION	FUTU	JRE CONSTR	UCTION	
DESIGNED W STANCILL	DRAWN W STANCILL	CHECKED W RICE	DATE 8/2016	DRAWING NO GR-TX-2016-002	SHEET 12 OF 12

Reporting	Ţ			
	,			
Start	Finish	Actual work	Actual duration	Exp
03/30/16	08/05/16	128	128	Turned in latest plans to USACE a
05/02/16	05/06/16	4	132	Completed.
05/09/16	06/24/16	46	178	Submitted. Waiting for SHPO app
05/09/16	06/24/16	0	178	In progress. On track.
05/09/16	06/24/16	0	178	Completed.
05/09/16	06/24/16	0	178	In progress. Development of MC
05/09/16	06/24/16	0	178	In progress. On track.
05/09/16	06/24/16	0	178	Completed.
05/09/16	09/23/16	137	315	Request submitted 05/03/2016.
09/26/16	12/31/16	96	411	Will only take about a week to do
01/01/17	03/31/17	5	416	Revegetate with native plans to a
		?		Dependant upon river flows/floo
		?		Dependant upon river flows/floo
		5 years	_	Dependant upon river flows/floo
	Reporting Start 03/30/16 05/02/16 05/09/16	Start Finish 03/30/16 08/05/16 03/30/16 08/05/16 05/02/16 05/06/16 05/02/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 06/24/16 05/09/16 03/31/16 09/26/16 12/31/16 01/01/17 03/31/17	Start Finish Actual work 03/30/16 08/05/16 128 05/02/16 05/06/16 4 05/09/16 06/24/16 46 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 06/24/16 0 05/09/16 09/23/16 137 09/26/16 12/31/16 96 01/01/17 03/31/17 5 ? ? ? ? 5	Start Finish Actual work Actual duration 03/30/16 08/05/16 128 128 05/02/16 05/06/16 4 132 05/09/16 06/24/16 46 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 06/24/16 0 178 05/09/16 09/23/16 137 315 09/26/16 12/31/16 96 411 01/01/17 03/31/17 5 416 1 ? ? . 1 <td< td=""></td<>

olanations

and Historical Commission.

proval of MOA.

OA with THC, SM, USFWS

In progress. On track. lo the work, but must be scheduled first avoid non-native intrusion oding events oding events

oding events